

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Incorporated.

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Hannah Pratt Well No. 1

Location: NE-NE-NE Sec. 28 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 4020' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clark was instructed to plug the well as follows:

249'--8 5/8" surface casing, cement circulated with 170 Sx.
391 1/4'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back indicated.

Run measuring line and find bottom. Sand back 50' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hyls, 30 sacks gel and 130 Sx. cement, staged.

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1969

CONSERVATION DIVISION
Wichita, Kansas

7-23-1969

Very truly yours,

M. L. Nichols
Conservation Division Agent