



15-179-20349-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1973
CONSERVATION DIVISION
Wichita, Kansas
3-6-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this
date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Dole Leasing Company.

Complete Address: Box #262, Russell, Kansas.

Lease Name: Laevenstein Well No. 1

Location: NW-NW-NE Sec. 1 Twp. 8 Rge. (E)(W) 27

County: Sheridan Total Depth 4081' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

246'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

K. L. D. Dible
Conservation Division Agent