



15-179-20262-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated, has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name: Haffner Well No. 1

Location: CSW-SW Sec. 3 Twp. 8 Rge. (E)(W) 27

County: Sheridan Total Depth 4045' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

216'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1175'.

Circulate hole with heavy mud. Pull DP to 1400' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1970
CONSERVATION DIVISION
Wichita, Kansas

8-24-70

Very truly yours,

M. L. Nichols
Conservation Division Agent