



15-179-20372-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

FEB 11 1974

CONSERVATION DIVISION Wichita, Kansas

2-11-74

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: National Oil Company,

Complete Address: 550 O. W. Garvey Building, Wichita, Kansas.

Lease Name: James Well No. 1

Location: CNE-NE Sec. 9 Twp. 8 Rge. (E)(W) 27

County: Sheridan Total Depth 4075' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx. Top of Dakota section @ 1175'.

Circulate hole with heavy mud. Pull DP to 1400' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols Conservation Division Agent