

State of Kansas



15-179-20393-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 21 1974

CONSERVATION DIVISION  
Wichita, Kansas

10-21-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: National Oil Company and Amarex, Incorporated,

Complete Address: Suite 550, 200 West Douglas, Wichita, Kansas.

Lease Name: Taylor Well No. 1

Location: 150' SE of CSE-SW-SE Sec. 11 Twp. 8 Rge. (E)(W) 27

County: Sheridan Total Depth 3900' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

210'---8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent