



15-179-20326-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 2
CONSERVATION DIVISION
Wichita, Kansas

10/2/72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated, has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Taylor Well No. B-1

Location: CW/2-SE-NE Sec. 23 Twp. 8 Rge. (E)(W) 27

County: Sheridan Total Depth 4256' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Draper was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section 2000'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 110 Cu. Ft. cement thru DP. Pull DP to 240' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

N. L. Dinkel
Conservation Division Agent