

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-179-20051-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
OCT 31 1967  
10-31-67  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Leo Lindenmuth of Chief Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Lindenmuth guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: P. O. Box #797, Great Bend, Kansas.

Lease Name: Taylor Well No. 1

Location: CSE-NE Sec. 24 Twp. 8 Rge. (E)(W) 27

County Sheridan Total Depth 3980' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Lindenmuth was instructed to plug the well as follows:

201'--8 5/8" Sueface pipe, cement circulated with--?  
Dakota section from 1025' to 850'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.  
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

M. L. Deibel  
Conservation Division Agent