


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 8 Twp. 8 Rge. 22 (E)      (W)       
Location as "NE/CNW/SW" or footage from lines SW SE SE  
Lease Owner Murfin Drilling Company  
Lease Name Schnebly Well No. 2  
Office Address 617 Union Center Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 13, 1955  
Application for plugging filed July 15 1961  
Application for plugging approved July 16 1961  
Plugging commenced July 17 1961  
Plugging completed July 25 1961  
Reason for abandonment of well or producing formation No longer producing in commercial quantities.  
If a producing well is abandoned, date of last production July 15 1961  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation      Depth to top      Bottom      Total Depth of Well 3524 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2" @	3515' w/	50 sx. cem.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Filled hole from 3524' to 3500 w/crushed rock.  
5 sx cement on rock @ 3500'  
Mixed 30 sx. Gel, followed w/20 sx. cement @450', pulled pipe to 175', mixed 10 sx Gel, followed w/20 sx cement; finished pulling pipe and plugged at 30' w/10 sx. cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Murfin Drilling Company  
Address 617 Union Center Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Fred Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Fred Murfin*  
617 Union Center Bldg., Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of April, 1962

*Jacqueline Zinn*  
Notary Public.

My commission expires 12/18/65



15-065-03251-00-00

# WELL LOG


COMPANY **Murfin Drilling Co.**  
FARM **Schnebly** NO. **2**

SEC. **8** T. **8** R. **22W**  
LOC. **SW SE SE**

TOTAL DEPTH **3524**  
COMM. **6-6-55** COMP. **6-13-55**

COUNTY **Graham**  
KANSAS

SHOT OR TREATED  
CONTRACTOR **Murfin Drlg. Co.**  
ISSUED



CASING  
20 10  
15 8 **177' w/150 sx. cement**  
12 6  
13 5 **3515' w. 50 sx. cement**

ELEVATION **2095 RB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

### Tops:

- 55 Sand
- 660 Shale - Shells
- 760 Shale - Sand
- 865 Sand
- 1260 Shale - Shells
- 1460 Sand
- 1714 Shale - Shells
- 1750 Anhydrite
- 2155 Shale - Shells
- 2390 Shale - Lime - Shells
- 3515 Lime - Shale
- 3524 Lime
- 3524 RTD

- Heebner 3311
- Toronto 3330
- LKC 3344

**RECEIVED**  
STATE CONSERVATION COMMISSION  
JUN 5 1962  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Sedgwick } ss:

I, W. R. Murfin of the Murfin Drilling Company  
upon oath state that the above and foregoing is a true and correct copy of the log of the Schnebly #2 well.

Subscribed and sworn to before me this 5th day of April

*[Signature]*  
62

My Commission Expires: 12/18/62

*[Signature]*  
NOTARY PUBLIC