

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,585 ²⁰/₈₀

LEASE NAME Jones

WELL NUMBER 1

SPOT LOCATION C SE 1/4

SEC. 8 TWP. 8 RGE. 22 (50 of (W))

COUNTY Graham

Date Well Completed 10/14/82

Plugging Commenced 9/20/84

Plugging Completed 9/20/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Helberg Oil Company

ADDRESS Box 32, Morland, Kansas 67650

PHONE # (913) 627-5665 OPERATORS LICENSE NO. 5669

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Carl Goodrow

Is ACO-1 filed? Yes If not, is well log attached? No - Not Available

Producing formation LKC Depth to top 3324 bottom 3534 T.D. 3681

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				4 1/2	3611	None
				8 5/8	180	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. All cement was 50/50 poz, 6% salt, & 3% Calcium chloride. Mixed 1 sack of gel, 3 sacks of hulls, & 50 sacks of cement followed by 15 sacks of gel & 45 sacks of cement, pumped down casing @ 1250 lbs. pressure & shut-in. Mixed 50 sacks of cement, 9 sacks of gel & 55 sacks of cement down annulus @ 150 lbs. pressure & shut-in. Job finished @ 10:00 A.M., 9/20/84.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pfeifer-Sharpe, Inc. License No. 6967

Address P. O. Box 386, Hill City, Kansas 67642

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Graham, ss.


William A. Daily (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) William A. Daily

(Address) Box 386, Hill City, Ks.

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1984

Debra L. Pfeifer-Wente
Notary Public



My Commission expires: May 12, 1986