

15-005-30/55-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 12 Twp. 8S Rge. (E) 22 (W)

Location as "NE/CNW%SW%" or footage from lines C NE NE

Lease Owner Chief Drilling Co., Inc.

Lease Name GORDON Well No. 1

Office Address Box 797 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/26, 66

Application for plugging filed 7/26, 66

Application for plugging approved 7/26, 66


Plugging commenced 7/26, 66

Plugging completed 7/26, 66

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Morland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	213	8-5/8"	213	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 600'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 200'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1966
7-27-66
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover
Box 797 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July 19 66

My commission expires Jan. 26, 1967.
Carmen R. Cook
Carmen R. Cook, Notary Public.

15-065-30155-00-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

GORDON #1
C NE NE SEC. 12-8S-22W
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 7-20-66
Completed: 7-26-66

Casing Record: 8-5/8" @ 213' w/175 sacks Common Cement & 2 sacks Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & Shale	0	60	2054 Gr.
Shale	60	455	2057 D.F.
Shale & Sand	455	1100	2059 K.B.
Sand	1100	1325	
Shale & Shells	1325	1500	<u>FORMATION TOPS</u>
Shale	1500	1600	Anhydrite 1600 + 459
Anhydrite	1600	1635	Topeka 3081 -1022
Shale	1635	1885	Heebner 3250 -1191
Shale & Shells	1885	2155	Toronto 3270 -1211
Shale & Lime	2155	3081	Lansing 3285 -1226
Lime	3081	3250	Base Kansas City 3492 -1433
Lime & Shale	3250	3285	Conglomerate 3612 -1553
Lime	3285	3492	Total Depth 3650
Shale & Lime	3492	3612	
Conglomerate	3612	3650	
Total Depth	3650		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE NE Section 12-8S-22W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 26th day of July, 1966.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1966
7-27-66
CONSERVATION DIVISION
Wichita, Kansas