


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-065-00917-00-00

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 1 Twp. 8S Rge. 23 XX (W)  
Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 SW/4  
Lease Owner Veeder Supply & Development Co. et al  
Lease Name Ellsworth Well No. 1  
Office Address Box 201, Cherryvale, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 18 19 56  
Application for plugging filed March 18 19 56  
Application for plugging approved March 18 19 56  
Plugging commenced March 18 19 56  
Plugging completed March 18 19 56  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3885 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	cemented w/125 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 205' with 1/2 sack hulls, 15 sacks cement; mud to 40' with 1/2 sack hulls, plug and 10 sacks cement; cemented to bottom of cellar

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Veeder Supply and Development Co.  
Address Box 201, Cherryvale, Kansas


STATE OF Kansas, COUNTY OF Montgomery, ss.  
Leo C. Veeder (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo C. Veeder  
Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 56

Lois Lawson  
Notary Public.

My commission expires July 11, 1956



3-23-56

15-005-00917-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Producers Pipe & Supply Company

Drilled for Veeder Supply & Development Co. Farm Ellsworth No. 1 Depth 3885  
 Contractor Veeder Supply & Development Co. Pipe 2 1/4" 8 5/8" csg. w/125 sacks  
 Location NW/4 NW/4 SW/4 Sec. 1 Twp. 8S Range 23W  
 Commenced 3-9-1956 Completed 3-18-1956 County Graham State Kansas

Shale and sand	0	130	130	TOPS FROM K. B.	
Shale	130	780	650	Topeka	3228
Shale and sand streaks	780	1200	420	Heebner	3437
Shale and shells	1200	1435	235	Toronto	3461
Sand and shale streaks	1435	1620	185	Lansing KC	3476
Red bed and shale	1620	1680	60	Base K. C.	3687
Shells and red bed	1680	1920	240	Arbuckle	3847
Shale anhydrite	1920	2030	110		
Shale and shells	2030	2500	470		
Shale and lime shells	2500	2622	122		
Shale and lime streaks	2622	2835	213		
Shale and lime	2835	3500	665		
Lime	3500	3805	305		
Lime and conglomerate	3805	3847	42		
Arbuckle	3847	3885	38		
T. D.	3885				

Dry and abandoned

AFFIDAVIT

STATE OF KANSAS )  
Montgomery County) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Ellsworth #1 well located in Section 1-8-S-23W. Graham County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By: Leo C. Veeder  
Leo C. Veeder

Subscribed and sworn to before me this 21st day of March, 1956.

Calvin Lawson  
Notary Public

My commission expires July 11, 1956.

**PLUGGING**  
 FILE SEC 1 T 8 R 234  
 BOOK PAGE 12 LINE 22

RECEIVED  
 STATE COMMISSION  
 MAR 21 1956  
 CONSERVATION  
 Wichita, Kansas  
 3-23-56