

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Graham County. Sec. 2 Twp. 8 Rge. (E) 23 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE NE NE

Lease Owner. Royer-Farris Drilling Co.

Lease Name. Jackson Well No. 1

Office Address. 709 Brown Bldg., Wichita 2, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed. June 7, 1947.

Application for plugging filed. June 6, 1947.

Application for plugging approved. June 7, 1947.

Plugging commenced. June 7, 1947.

Plugging completed. June 7, 1947.

Reason for abandonment of well or producing formation. Dry

If a producing well is abandoned, date of last production. 19    

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough, Hays, Kansas.

Producing formation. Depth to top. Bottom. Total Depth of Well. 3935 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Soil	Sand & Soil	0	130	10 3/4	130	None
		Cemented with 100 sax top to bottom				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Started out of hole pumping extra heavy mud on bottom as drill pipe was laid down.  
Set bridge plug at 125 ft. and cemented it with 15 sax cement, filled on up with mud  
and set bridge plug at 20 ft. and cemented it with 10 sax cement to top and cut off  
pipe below plow depth.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Royer-Farris Drilling Company  
Address. 709 Brown Building, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss. L. A. Farris

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]

709 Brown Bldg., Wichita 2, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of June, 1947.

My commission expires. April 23, 1949.

Effie J. Hoote  
Notary Public.



JUN 12 1947

JACKSON #1 NMc Section 2, Township 3, South, Range 23, West,  
Graham County, Kansas.

Drilling Contractor: Hoyer-Farris Drilling Co.  
Drilling Started: May 25, 1947.  
Drilling Completed: June 7, 1947.  
Set 133' of 10 3/4" surface pipe  
cemented with 100 sacks cement.

0	161	Shale and shells
161	340	shale
340	429	chalk line
429	670	dark shale
670	860	shale
860	940	red bed and shale
940	1120	dark shale
1120	1275	shale and shells
1275	1680	shale and red bed
1680	1819	red bed and gyp
1819	1959	anhydrite
1959	2000	shale
2000	2186	shale shells and red bed
2186	2250	shale and shells
2250	2360	shale and red bed
2360	2438	line
2438	2603	shale and red bed
2603	2948	line and shale
2948	3050	line
3050	3395	line and shale
3395	3435	line
3435	3559	line and shale
3559	3802	line
3802	3849	line and shale
3849	3865	shale
3865	3935	line and shale

Measurements From top rotary bushing:

Top Kober Shale	3475
Top Lansing	3511
Base Lansing	3727
Marmaton	3727-3865
Conglomerate	3864-3904
Top Arbuckle	3904
Total Depth	3935

No Shows

Dry and Abandoned.

L. A. Farris does hereby swear that he is a partner of the firm,  
Hoyer-Farris Drilling Company, who were the drilling contractors on the above described  
well and that the above log is true and correct to the best of his knowledge and belief.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

BE IT REMEMBERED, That on this 10th day of June, A. D. 1947, before me,  
a Notary Public in and for said County and State, personally appeared L. A. Farris, to  
me known to be the identical person described in and who executed the within and fore-  
going instrument and acknowledged to me that he executed the same as his free and volun-  
tary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my official signature and af-  
fixed my notarial seal, the day and year first above written.

*Effie J. Hoote*  
Notary Public

My Commission expires April 23, 1949.

