

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

RECEIVED
OCT 06 2003
OCT 06 2003
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

15-065-20240-00-02

Lease Operator: DaMar Resources, Inc.

Address: P. O. Box 70 Hays, KS 67601

Phone: (785) 625 - 0020 Operator License #: 9067

Type of Well: Enhanced Recovery Docket #: E-19,121
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: approx. 9/10/03 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing Depth to Top: 3517 Bottom: 3720 T.D. 3730
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-20,923

Lease Name: Montgomery

Well Number: 3

Spot Location (QQQQ): C - S/2 - S/2 - SW
330 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 2 Twp. 8 S. R. 23 East West

County: Graham

Date Well Completed: 6/11/77

Plugging Commenced: 9/15/03

Plugging Completed: 9/15/03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surf	247	8 5/8	247	none
		surf	3755	5 1/2	3755	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Mix 285 sx 60-40 pozmix cement w/10% gel. Pump down 5 1/2" casing - 40 sx neat, 60 sx w/600# hulls,
185 sx neat, max pressure 860#, shut in pressure 300#. Pressure up on 8 5/8 - 5 1/2 annulus, held 300# steady.

Name of Plugging Contractor: DaMar Resources, Inc. License #: 9067

Address: P. O. Box 70 Hays, KS 67601

Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.


State of Kansas County, Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 70 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 3rd day of October, 2003

Vickie Cole My Commission Expires: 10-18-04
Notary Public