

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 4 TWP. 8s RGE. 23w E/W
Location as in quarters or footage from lines:
NW NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner A. Scott Ritchie
Lease Name Jones "D" #1 Well No. _____
Office Address 125 N. Market, Suite 950, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 1/6/83
Plugging completed 1/13/83
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
Producing formation _____ Depth to top _____ bottom _____ T.D. 3825'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	167'	none
				4 1/2"	3824'	1453'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged bottom with 4 sacks cement, sand to 3046' & 4 sacks cement. Shot
well at 2913', 2819', 2634', 2424', 2313', 2134', 1916', 1712', & 1515'.
Pulled 34 joints. Plugged well with 2 sacks hulls mixed with 29 gel, 100
sacks cement, 11 gel, 70 sacks cement, & 8 5/8 plug.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1983



My Commission expires: _____

Irene Hoover
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1983

CONSERVATION DIVISION
Wichita, Kansas

120-83

15-065-21658-00-00

WELL LOG

COMPANY A. Scott Ritchie

SEC. 4 T. 8S R. 23W
LOC. NW NW SE

FARM Jones "D" NO. 1

RIG. NO. 21

TOTAL DEPTH 3825'


COMM. 7-11-82

COMP. 7-16-82

Graham

COUNTY

KANSAS



CONTRACTOR

Murfin Drilling Company

CASINO

20
15
12
13

10
8-5/8" csg set @ 167' w/145sx common quickset
6
5

PRODUCTION

4 1/2" csg set @ 3824' w/125 sx 60-40 Poz, 10% salt

FIGURES INDICATE BOTTOM OF FORMATIONS

Soil & Sand	50'
Shale	168'
Shale & Sand	1967'
Anhydrite	2001'
Shale	2680'
Shale & Lime	3825'

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1982

CONSERVATION DIVISION
Wichita, Kansas

11-15-82

State of KANSAS
County of SEDGWICK } ss:

I, David L. Murfin of the Murfin Drilling Company

do hereby state that the above and foregoing is a true and correct copy of the log of the Jones "D" #1 well.

RAMONA GUNN
STATE NOTARY PUBLIC
Sedgwick county, K.
My Appt. Exp. 1-25-84

David L. Murfin

Subscribed and sworn to before me this 9th day of August 19 82

My Commission Expires: 1-25-84

Ramona Gunn
NOTARY PUBLIC