


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-065-00506-00-00

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County, Sec. 5 Twp. 3 Rge. 23 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW 1/4 SW
Lease Owner Burch Drilling Co., Inc.
Lease Name Montgomery #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8-31-58 _____ 19____
Plugging completed 9-3-58 _____ 19____
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	none
				4-1/2"	3744'	3286'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3685' and found it open. Filled w/sand to 3500' and dumped 3 saks of cement. Pulled 4 1/2" casing, cleared hole and mudded to 200', set 10' rock bridge and ran 25 sacks of cement. Mudded the hole to 40', set 10' rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

Name of Plugging Contractor West Supply Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE
I, Noel J. Knight, SS. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of September, 1958

Thomas V. Dager
Notary Public.

My commission expires 9-27-58

PLUGGING
FILE SEC S.T. 2 R 23W
BOOK PAGE 121 LINE 4

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1958
9-6-58
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15-065-00506-00-00

Burch Drilling Co., Inc.
#1 Montgomery
NW NW SW 5-8S-23W
Graham County, Kansas
Comm. 5-5-58
Comp. 5-29-58

8 5/8" @ 225' with 160 sx.
4 1/2" @ 3744' with 125 sx.
Elevation: 2248 KB

1755 Shale & Shells
1900 Shale
1933 Anhydrite
3560 Lime
3590 Cherty Lime
3745 Lime

3745 TD

Tops:

Heebner 3474
Toronto 3490
Lansing 3503
BKC 3710

DST #1 3540-90. 1 hr. Rec. 50'
heavy oil cut mud, plus 101' very heavy
oil cut mud, plus 37' oil cut salt water.
FBHP (30 min.) 1095#/

DST #2 3628-60. 1 hr. Rec. 40'
very slightly oil cut mud. FBHP 119#.

DST #3 3660-3700. 1 hr. Rec. 25'
mud. FBHP 62#.

STATE OF KANSAS:
COUNTY OF SEDGWICK:

I, Earl M. Burch, of the Burch Drilling Co., Inc. being first duly sworn on
oath, state: That I have knowledge of the facts, statements and matters herein contained
and that the same are true and correct.

Earl M. Burch

Earl M. Burch

Subscribed and sworn to before me this 22nd day of June, 1958.

My commission expires: July 27, 1960

Larry Harrison
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1958

8-6-58

PLUGGING
FILE SEC 5 T 8 R23W
BOOK PAGE 121 LINE 4