

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-065-20,724-00-00

LEASE NAME Montgomery #1

WELL NUMBER NW SW SW

         Ft. from S Section Li

         Ft. from E Section Li

SEC. 5 TWP. 8S RGE. 23W(E) or (I)

COUNTY Graham

Date Well Completed         

Plugging Commenced 4/24/85

Plugging Completed 4/24/85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR A. Scott Ritchie

ADDRESS 125 N. Market, Suite 950, Wichita, Ks. 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 5198

Character of Well         

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3767'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	128'	none
				4 1/2"	3767'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each set.

Plug job only - No pipe recovery. Ran tubing to top of sand @ 3720' & pumped 50 sacks cemer  
 Pulled tubing to 2980' & pumped 50 sacks cement. Pulled to 2140' & pumped 50 sacks  
 cement. Pulled to 1400' & pumped 30 sacks with 3 gel, cement circulated. Pulled tubing  
 out, tied on to 8 5/8 & pumped 10 sks cement, 17 gel, 2 hulls, 50 cement, swedged long  
 (if additional description is necessary, use BACK of this form.) (OVER)

Name of Plugging Contractor Poe Well Service License No. 6779

Address Box 115, Oberlin, Ks. 67749

STATE OF Kansas COUNTY OF Decatur, ss.

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Marvin R. Poe (Pres)

(Address) Box 115 Oberlin Ks

SUBSCRIBED AND SWORN TO before me this 25 day of July, 1985

Notary Public

COPY



RECEIVED  
 STATE CORPORATION COMMISSION  
 1986

2915  
 17-29-85

Form CI  
 Revised 08-

string in & pumped 50 sacks of 50/50 poz 6% gel 3% c.c.

Plugging complete.