


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 6 Twp. 8S Rge. 23 (E) W (W)
Location as "NE/CNW/SW" or footage from lines ~~SW SW~~ Approx. C NW SW
Lease Owner Alco Oil & Gas Corporation
Lease Name Nicholson Well No. 1
Office Address Box 299 520 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 5 19 61
Application for plugging filed December 5 19 61
Application for plugging approved December 5 19 61
Plugging commenced December 5 19 61
Plugging completed December 5 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4014 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	218'	8-5/8"	218'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1961
12-13-1961
CONSERVATION DIVISION
Wichita, Kansas

4014' to 600' - Heavy rotary mud
600' to 538' - 20 sacks cement and plug
538' to 180' - Heavy rotary mud
180' to 118' - Plug and 20 sacks cement
118' to 40' - Heavy rotary mud
40' to 6' - 1/2 sack hulls, plug and 10 sacks cement
6' to 0 - Cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PEEL BROTHERS, INC.
Address P. O. Box 359 Hoisington, Kansas

STATE OF KANSAS, COUNTY OF GRAHAM, ss.
Peel Brothers, Inc. (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY Handell G. Peel
P. O. Box 359 Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of December, 19 61

Ruth Brant
Notary Public.

My commission expires April 27, 1964



DRILLERS' LOG

Well Owner: Alco Oil & Gas Corporation
 Farm Name: Nicholson Well No. 1
 Total Depth 4014'
 Commenced: 11/26/61
 Completed: 12/5/61
 Contractor: Peel Brothers, Inc.
 Casing: 8-5/8" @ 218' cem.

~~xxx~~ Approx. C NW SW
 Sec. 6, Twp. 8S, Rge. 23W
 Graham County,
 Kansas
 Elevation: 2295 K.B.
 Production: Dry

Figures below indicate bottoms of formations:

Post Rock	0 -	35
Shale		400
Shale & sands		1175
Shale		1250
Sand & shale		1500
Sand		1720
Shale & red bed		1800
Shale		1958
Anhydrite		1990
Shale		2535
Shale & lime streaks		2705
Lime & shale		3365
Lime		3545
Lime & shale		3600
Lime		3660
Lime & shale		3735
Lime		3790
Shale		3870
Lime & shale		3900
Shale & chert		3962
Lime		4014
Total Depth		4014

RECEIVED
 CONSERVATION DIVISION

12-13-1961
 CONSERVATION DIVISION
 Wichita, Kansas

This is to certify that the above information is to the best of my knowledge, true and correct.

PEEL BROTHERS, INC.

BY Andrew G. Peal

SUBSCRIBED AND SWORN to before me this 11th day of December, 1961.

My commission expires: April 27, 1964

Rich Brant
 Notary Public