

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1973
MAR 6 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rider of K & E Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Incorporated.

Complete Address: 816 Union Center, Wichita, Kansas.

Lease Name: Stuchlik Well No. 1

Location: CNE-NE Sec. 7 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3660' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Rider was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 250 Sx.
3659'--4 1/2" Production casing cemented on bottom with 125 Sx. DV Tool
set @ 1890' with Chem Pak. Well plugged back to 3200'. 4 1/2" has been
squeezed in the Cedar Hills 3 separate times.

Attempt to pump down annulus to determine if it can be squeezed. Squeeze
4 1/2" with 175 Cu. Ft. 50/50 Pozmix w/6 % Gel.

Very truly yours,

M. L. F. Nichols
Conservation Division Agent