

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 4 - 1972  
MAY 4 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Warren Davis of Hellar Drlg., Co., Inc., has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Landes Exploration Company,

Complete Address: Box #867, Magnolia, Arkansas.

Lease Name: Casey Jones Well No. 1

Location: SW-NW-SW Sec. 7 Twp. 8 Rge. (E)(W) 22

County: Graham Total Depth 3486' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 550'.

Circulate hole with heavy mud. Pull DP to 775' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*M. L. Nichols*

Conservation Division Agent