

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1963
Dec 16, 1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:
Imperial Oil of Kansas, Inc.,
Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil of Kansas, Inc.,
Complete Address: 780 4th National Bldg., Wichita, Kansas.
Lease Name: Dreiling Well No. A-2
Location: NW-NE-SW Sec. 29 Twp. 8 Rge. (E) (W) 22
County Graham Total Depth 3644 Oil Well X
Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:
222'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3642'--5 1/2" Production casing cemented with 100 Sx.
Plugged back to 3509'. Top perforations 3501' to 3503'.

Sand well back to 3490' and set 4 Sx cement with dump bailer.
Pull 5 1/2" to 600' & circulate heavy gel mud, Pull 5 1/2" to 540'
and displace 20 Sx cement thru 5 1/2". Pull 5 1/2" to 210' and
displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge
@ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,
W. L. Nichols