

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

NOV 6 1967  
NOV 6 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co. Inc has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: 1860 Lincoln Street, Denver, Colorado.

Lease Name: J. M. Moore Well No. 1

Location: SW-SW-NW Sec. 29 Twp. 8 Rge. (E)(W) 22

County Graham Total Depth 3700 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Unruh was instructed to plug the well as follows:

238'--8 5/8" Surface pipe, cement circulated with 180 Sx.  
3699'--5 1/2" Production casing cemented on bottom with 150 Sx. Bridge  
plug @ 3683'. Top perforations from 3566' to 3570'. Staging collar  
set @ 3149' and oil circulated to surface.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull  
5 1/2" casing and squeeze well with 35 sacks gel plus 5 sacks hulls and  
130 Sx. cement.

Very truly yours,

H. L. Nichols  
Conservation Division Agent