

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 31 1967
OCT 31 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: 1860 Lincoln Street, Denver, Colorado.

Lease Name: J. M. Moore Well No. 2

Location: NE-SW-NW Sec. 29 Twp. 8 Rge. (E)(W) 22

County Graham Total Depth 3700 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

235'--8 5/8" Surface pipe, cement circulated with 165 Sx.
3700'--5 1/2" Production casing cemented on bottom with 150 Sx. Stage collar set @ 3145' with oil circulated to surface. Well plugged back to 3658'. Top perforations from 3506' to 3512'.

Sand well back to 3490' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well 35 Sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent