


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Graham County, Sec. 24 Twp. 8 Rge. 22 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SE
Lease Owner Shields Oil Producers, Inc.
Lease Name Gosselin "A" Well No. 1
Office Address Shields Building, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 30, 1969
Application for plugging filed May 30, 1969
Application for plugging approved May 30, 1969
Plugging commenced May 30, 1969
Plugging completed May 30, 1969
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichol
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,695 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	192'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole w/ heavy mud
Set bridge plug @ 805'
Pump 70 sax cement on plug thru 4 1/2" drill pipe
Set bridge plug @ 215'
Pump 20 sax cement on plug thru 4 1/2" drill pipe
Fill hole w/ heavy mud
Set bridge plug @ 40' w/ 1/2 sax hulls on plug
Dump 18 sax cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1969

CONSERVATION DIVISION
Wichita, Kansas

06-25-1969

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shields Drilling Co., Inc.
Address Shields Building, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
R. J. Shields (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Shields
Shields Building, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 1969

My commission expires May 26, 1971
Ruth Phillips Notary Public

Shields


Russell, Kansas

WELL LOG

15-065-20228-00-00

Operator: Shields Oil Producers, Inc.
 Well: Gosselin "A" #1
 Commenced: May 23, 1969
 Completed: May 30, 1969
 Contractor: Shields Drilling Co., Inc.

Well Description: NE SE
 Sec. 24-8S-22W
 Graham Co., Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	192'	Cmtd. w/ 175 sax

Elevation: 2,094' RB

Treatment:

Production: D & A

Tops:

Heebner	3,286'
Toronto	3,310'
Lansing-KC	3,324'
Conglomerate	3,615'
Arbuckle	3,673'

..... Figures Indicate Bottom of Formations

Shale	200'
Shale & sand	1,330'
Shale & redbed	1,648'
Anhydrite	1,695'
Shale & shells	2,015'
Shale & lime	3,320'
Lime	3,695' RTD

NOTES

DST #1	3,345' - 3,375'	Tool open 1 hr. w/ weak blow for 5 min. Recovered 15' mud. IBHP-1, 275#, IFP-52#, FFP-57#, FBHP-1, 232#/30 min.
DST #2	3,390' - 3,412'	Tool open 1 1/2 hrs. w/ weak steady blow thruout. Recovered 260' muddy water. IBHP-1, 302#, IFP-52#, FFP-187#, FBHP-1, 164#/30 min.
DST #3	3,440' - 3,500'	Tool open 1 hr. w/ weak blow thruout. Recovered 80' SOCM. IBHP-1, 326#, IFP-51#, FFP-103#, FBHP-1, 105#/30 min.
DST #4	3,628' - 3,658'	Tool open 1 hr. w/ weak blow for 11 min. Recovered 10' mud. IBHP-85#, IFP-35#, FFP-42#, FBHP-59#/30 min.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 25 1969
 CONSERVATION DIVISION
 Wichita, Kansas