


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-02152-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 28 Twp. 8 Rge. 22 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner Honaker-Davis Drlg. Co.  
Lease Name Pierce Well No. 1  
Office Address 2008 Lakin, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-30 19 56  
Application for plugging filed 6-29 19 56  
Application for plugging approved 6-29 19 56  
Plugging commenced 6-30 6:00 A.M. 19 56  
Plugging completed 6-30 8:00 A.M. 19 56  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3916 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	207	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 200' with heavy rotary mud. Dumped in 1/2 sacks of hulls-set plug. Mixed 15 sacks of cement by hand and poured in through drill pipe.

Filled hole to 40' with heavy rotary mud. Dumped in 1/2 sack of hulls-set plug. Mixed 10 sacks of cement by hand. Filled hole with cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker-Davis Drlg. Co.  
Address 2008 Lakin, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
S. C. Lingreen (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen  
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 56

Kenneth G. Fisher Notary Public.

My commission expires 6-25-59

PLUGGING  
FILE SEC 28 T 8 R 22 W  
BOOK PAGE 76 LINE 6

07-10-1956

15-065-02152-00-00


DRILLERS LOG

Pierce No. 1  
Loc: NW NW NW  
Sec: 28-35-22W  
Graham County, Kansas  
Company: Honaker-Davis Dril. Co., et al  
Contractor: Honaker-Davis Dril. Co.

Comm: 6-19-56  
Comp: 6-30-56  
Rotary Total Depth: 3916  
Casing: 8-5/8" at 207'  
D & A

0	60	Sand	
60	150	Clay	
150	210	Blue Shale	8-5/8" casing cemented at
210	775	Shale	207' with 175 sacks cement
775	900	Sand & Shale	and 4 sacks calcium chloride
900	1830	Red Bed & Shale	
1830	3430	Lime & Shale	
3430	3505	Lime	
3505	3520	Lime & Chert	
3520	3635	Lime	
3635	3657	Lime & Shale	
3657	3670	Sand	
3670	3710	Lime & Shale, Sand	
3710	3750	Lime & Shale	
3750	3785	Lime & Chert	
3785	3830	Lime & Shale	
3830	3875	Chert & Lime	
3875	3916	Lime & Shale	D & A
3916		Total Rotary Depth	

I certify that this is the true and correct copy of the above log to the best of my knowledge.

  
H. S. Forbes

Subscribed and sworn to before me this 9th day of July, 1956.

  
Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING  
FILE SEC 28 T 3 R 22W  
BOOK PAGE 76 LINE 6