

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 7-30-54-Drilling Date

15-065-01696-00-02

LEASE NAME FINK

DEC 3 1984

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

SPOT LOCATION 1650' FWL-900' ESL

SEC. 27 TWP. 8 SRGE. 22 (NW) 4

COUNTY Graham

Date Well Completed 9-29-75

Plugging Commenced 11-20-84

Plugging Completed 11-20-84

LEASE OPERATOR FELL OIL & GAS COMPANY

ADDRESS P.O. BOX 9487 TULSA, OKLAHOMA 74157

PHONE # (918-446-6114) OPERATORS LICENSE NO. 6718

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita & Hays

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Cedar Hills Depth to top 1353' bottom 1414' T.D. 1500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cedar Hills	Salt water	0	160'	8-5/8"	160'	0
		0	3713	5 1/2"	3713'	0
		0	1500	2 1/2"	1500'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Swedged on to 8-5/8" casing. Halliburton took inj. rate with water @ 3 1/2 BPM @ 250#. Mixed 225 sx 50/50 Poz. 6% Gel 3% CC. Pumped down well. Hole standing full. Waited 30 min. Mixed 75sx 50/50 Poz. 6% Gel 3% CC. Pumped down well @ 1BPM @ 300#. Shut down. Hole standing full.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor N/A License No. N/A
Address _____

STATE CORPORATION COMMISSION

JAN 17 1985

JAN 17 1985

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Bruce L. Taton

(employee of operator) or Wichita, Kansas

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bruce L. Taton

(Address) P.O. Box 9487
Tulsa, OK 74157

SUBSCRIBED AND SWORN TO before me this 3rd day of December, 1984

Gloria A. Sam

Notary Public

My Commission expires: 2/14/88

Gloria A. Sam