

A. D. ALLISON et al.
FULK #1

Total Depth: 3288'
Comm: 3-6-51
Comp: 3-23-51
CONTR: A. D. ALLISON & CO., INC.

Sec. 11, Twp. 27S., Rge. 2E.
SE SW SE
Sedgwick County, Kansas.
Elev: 1332 D. F.

CASING RECORD:


8-5/8 126'

FORMATION	DEPTH
Gypsum	105
Shale and shells	124
Lime, broken	135
Lime and shale	170
Lime	320
Lime and shale streaks	485
Lime and shale	915
Shale and shells	1410
Lime and shale	1565
Lime and shale streaks	1670
Shale	1680
Shale and lime streaks	1740
Shale and shells	1970
Shale	2030
Lime	2157
Lime, broken	2275
Lime	2330
Shale and shells	2400
Lime	2549
Lime, broken	2630
Lime and shale	2695
Lime and shale streaks	2743
Shale and shells	2775
Shale	2860
Lime	3015
Lime and shale	3050
Lime, broken	3092
Shale	3137
Dolomite	3145
Simpson dolomite	3165
Sand	3195
Shale and sand	3230
Sand and shale	3247
Sand	3251
Lime, Arbuckle	3257
Sand and shale	3271
Lime	3288 - T. D.

TOPS:

Lansing	2386
Mississippi	2860
Viola	3137
Simpson dolomite	3157
Simpson sand	3162
Arbuckle	3245

Perforated 3247-3251.
Potential 144.36 bbls.
Well went to water.



IVED
RATION COMMISSION