

R


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sedgwick County. Sec. 14 Twp. 27 Rge. 2 (E) 1/WV

Location as "NE/CNW/SW" or footage from lines C of NE SE
Lease Owner Jimmy Raymond Oil Company
Lease Name Razook Hoult Well No. 3
Office Address 410 Fourth Nat'l Bank, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed 9-11 19 62
Application for plugging approved 9-12 19 62
Plugging commenced 9-12 19 62
Plugging completed 9-17 19 62
Reason for abandonment of well or producing formation Low production



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3238 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	90	none
				7"	3232	2217.45

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with gravel to 3232 feet, dumped 5 sacks cement.
Set 10 foot rock bridge at 180 feet, dumped 25 sacks cement.
Mudded hole to 30 feet. Set 5 foot rock bridge
Dumped 8 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
9-25-62
SEP 25 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kent Well Servicing Co., Inc.
Address Box 470, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Mary Payne

(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 62

My commission expires June 10, 1963

Esteban E. Phelps
Notary Public.



WELL LOG - HOULT #3

Q

OPERATOR: J. P. Gaty,
11 Cypress Drive,
Forrest Hills,
Wichita, Kansas.

Jimmy Pazoob
Invoice Raymond Co

LOCATION: C/E/2 NE/40 SE/4
Section 14-27S-2
Sedgwick County,
Kansas.

CONTRACTOR: Morrison Drilling Company, Inc.,
Drawer 712,
El Dorado, Kansas.

PRODUCTION: _____

Farm: Hoult Well No. 1 Field:

Date Commenced: February 23, 1954
Date Completed: March 5, 1954

Elevation: _____

Total Depth: 3232½ Rotary

CABLE TOOL LOG

From	To	Formation	
0	90	Cement	Rotary T. D. (corrected) 3231½.
90	210	Lime	
210	580	Lime and Shale	3231½-3233 Sandy shale.
580	1080	Shale W/Lime Streaks	3233-3243½ Arbuckle dolomite.
1080	1260	Shale and Lime	Oil @ 3239.
1260	1460	Shale and Lime	
1460	1600	Lime and Shale	
1600	1620	Shale and Lime	
1620	1680	Lime and Shale Streaks	
1680	2040	Lime and Shale	
2040	2070	Lime	
2070	2110	Lime and Shale	
2110	2175	Shale and Lime	
2175	2240	Lime	
2240	2370	Lime and Shale Streaks	
2370	2395	Lime and Shale	
2395	2500	Lime	
2500	2707	Lime and Shale	
2707	2711	Shale and Lime	
2711	2830	Lime and Shale	
2830	2841	Lime and Chert	
2841	2948	Lime and Chert	
2948	3093	Lime	
3093	3129	Lime and Shale	
3129	3151	Lime, Sand and Shale	
3151	3159	Sand Stone and Lime	
3159	3176	Sand Stone	
3176	3214	Lime	
3214	3232½	Sandy Shale	
3232½		Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1962
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Hoult #3 well drilled for Mr. J. P. Gaty and completed March 5, 1954.

MORRISON DRILLING COMPANY, INC.

C. W. Wilson
C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS 0
) ss:
COUNTY OF BUTLER 0

SUBSCRIBED AND SWORN TO, Before the Undersigned, A Notary Public, in and for the County and State aforesaid this 8th day of March, 1954.

Ann Biles
Notary Public

My Commission Expires January 10, 1955.