


LOG OF WELL

SHEET NO. 2

District	Kansas	Owner	The Texas Co	Farm	M. C. Devine	Well No.
FORMATION		AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Surface Soil		115				
Shells & Blue Slate	136	21				
Shale & Shells	165	29				
Sand	175	10				
Shale & Shells	370	195				
Lime	395	25				
Shale, Shells-Lime	530	135				
Lime & Shale	565	35				
Shale & Shells	620	55				
Lime	648	28				
Sand	665	17				
Shale & Shells	705	40				
Lime	719	14				
Shale	735	16				
Lime & Shale	745	10				
Lime	768	23				
Shale	773	5				
Lime	810	37				
Lime & Shale	855	45				
Shale, Lime Streaks	960	105				
Shale & Lime Shells	1054	94				
Sandy Shale	1065	11				
Sand & Shale	1112	47				
Sandy Lime	1128	16				
Sandy Shale	1164	36				
Broken Lime	1245	81				
Shale & Lime Shells	1362	117				
Lime	1372	10				
Lime & Shale	1490	118				
Lime, Broken	1538	48				
Shale & Lime	1572	34				
Lime	1588	16				
Lime & Shale	1604	16				
Lime	1644	40				
Shale	1664	20				
Sand & Iron Streaks	1682	18				
Lime	1738	56				
Shale & Shells	1758	20				
Lime	1806	48				
Shale & Lime	1838	32				
Broken Lime	1874	36				
Lime & Shale	1904	30				
Lime	1926	22				
Lime & Shale	1958	32				
Sand	1988	30				
Sand & Sandy Shale	2015	27				
Shale	2082	67				
Lime & Shale Streaks	2118	36				
Lime	2154	36				
Shale	2184	30				
Lime	2276	92				
Shale & Shells	2370	94				
Shale	2462	92				
Lime	2685	223				
Shale & Lime Streaks	2734	49				
Lime	2780	46				
Lime, Broken	2860	80				
Broken Lime & Shale	2936	76				
Miss. Lime	2960	24				
Lime	3008	48				
Lime & Shale Breaks	3040	32				
Lime	3058	18				
Lime & Shale Streaks	3080	22				
Lime & Shale	3230	150				
Sand & Shale	3237	7				



LOG OF WELL

SHEET No. 3

District Kansas Owner The Texas Co Farm M. C. Devine Well No. 1

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
(CONTINUED)					
Sandy Lime	3240	3			Elevation.....1349'
Shale & Lime	3280	40			TOPS:
Lime & Sand	3288	8			Lansing.....2130'
Sandy KiMM Shale	3303	15			Kans City.....2454'
Hardwhite Sand	3307	4			Mississippi....2931'
Sand & Lime	3310	3			Simpson.....3232'
Lime	3330	20			Arbuckle.....3301'
Hard Lime	3347	17			CASING RECORD:
Soft Lime	3354	7			8-5/8" OD 28# LW Set
Soft Lime	3356	2			at 118' w/ 50 sax
Corr Sch Depth	3350'				cement & 15 sax cement around top of cas-
Total Depth	3350'				ing.

REMARKS:

Ran DST, set packer at 3226' w/ 14' anchor, open 30 minutes, filled up 2400' w/ salt water - Ran Schlumberger, 4/8/47, no show.