

UNION NATIONAL BANK BLDG WICHITA KANSAS.

Location SW corner. Sec. 17 T. 27 R. 2E.
162' fr WL 348' fr SL.

Casing Record 10" 1485 Farm- Davies County- Sedgwick.
No. 1

20" 8 1/2" 2635 Company- The Ramsey Petroleum Co., et al.
15 3/8" 115 65/8" 2949 Contr.-
12 3/8" 1038 53/16" Coma.- 10/29/30 Comp.- 12/16/30

Total Depth 2988'. Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.
Date Issued. 12/27/1930.

Elevation Initial Production 720 bbls.

Formation	Depth	Formation	Depth	Formation	Depth
collar	10	slate drk	1255	shale	2805
slate	80	8 BW 1165		lime grey	2818
7 BW 50-55'		lime grey	1270	shale	2823
lime lgt	85	slate white	1280	lime grey	2828
slate	95	lime grey	1290	shale	2835
slate & shells	150	slate lgt	1295	slate shells	2850
lime white	160	slate drk	1405	pink rock	2855
slate lgt	175	lime white	1440	lime white	2870
lime lgt	180	2 BW 1405-20		slate drk	2910
slate lgt	215	slate drk	1450	lime grey	2920
lime lgt	235	lime white	1455	slate	2945
slate lgt	240	slate drk	1460	brkn lime &	
slate & shells	305	lime white	1490	slate	2950
lime white	315	slate drk	1525	chat & slate &	
slate drk	340	lime	1530	show of oil	2953
slate lgt	350	shale lgt	1535	chat & slate &	
lime lgt	385	lime white	1580	lime	2961
slate & lime	435	slate drk	1615	chat & lime	2985
lime white	485	lime white	1625	lime more chat	2987
slate	510	slate drk	1635	chatty lime	2988
lime grey brkn	565	lime white	1645		
lime white	585	slate shells	1665	Total Depth	2988'
slate drk	590	lime white	1675		
red rock	600	slate lgt	1725		
slate shells	625	lime grey	1730		
red rock	635	slate lgt	1745		
lime & slate	680	lime grey	1770		
lime white	690	slate lgt	1775		
slate shells	720	lime white	1915		
lime white	740	1 BW 1800-10'			
slate shelly lime	760	slate drk	1918		
lime grey	765	lime white	1923		
slate drk	775	slate drk	1940		
lime grey	785	lime white	1960		
slate drk	793	slate drk	1975		
lime	795	lime white	1980		
slate shells	860	slate drk	2030		
slate drk	865	slate sdy	2145		
lime slate breaks	890	lime	2150		
slate grey	895	slate drk	2170		
lime grey	908	lime grey	2210		
slate drk	915	slate drk	2295		
slate lgt	950	lime white	2310		
lime shells	955	slate drk	2320		
slate drk	1000	slate shelly	2375		
shale lgt	1010	lime	2430		
HW 1010-38'		slate drk	2440		
water sand lgt	1035	lime shells	2442		
lime lgt	1038	shale lgt	2495		
slate shells	1115	lime	2618		
lime	1120	slate drk	2620		
slate	1125	lime white	2680		
sdv shale	1145	slate drk	2710		
lime & shale	1150	lime grey	2725		
shale	1165	shale & lime	2740		
lime lgt	1175	shale & lime shells			
shale lgt	1200		2750		
slate black	1210	lime grey	2755		
lime	1235	slate shells	2800		
4 BW 1125-35'					