

15-173-00904-00-00

12-10-35
rec'd

11 27 2E
25-8

To
State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

File No. 25-8

Location SEc

Sec. 11 Twp. 27 Rge 2E

I have today completed supervision of plugging of

Well No. 1 Lease Bessie Chase

Operator Dickey Oil Company

Field _____ County Sedgwick

Total Depth 3278 Feet.

(Describe briefly the manner in which well was plugged)

When the 5 3/16" casing was landed it was cemented with twenty sacks of cement. In plugging it was cut off with a Eureka casing knife at 2780, then the casing was pulled out. At the time the 6 5/8" casing was landed, it was cemented with fifteen sacks of cement. In plugging it was cut off at 2772 and the hole was mudded with fifty pails of good heavy mud before pulling. As each joint was pulled two more pails of mud were added for the first fifty joints. The total 2850 feet of 8 1/4" casing was pulled. When the 10" casing was started at 2290 feet, fifty pails of heavy mud were dumped into the hole. The 12 1/2" and 15 1/2" casing was also pulled. The hole was then bridged with a wood plug at 160 feet, then ten feet of rock, one yard of river sand, and fifteen sacks of Ashgrove cement were added. The cement was allowed to set three days. The hole was then filled with heavy

Expense incurred as follows: Con't. on back)

Date _____ *Day 1/4 Mileage 18

Date _____ *Day 1/4 Mileage 18

Date _____ *Day _____ Mileage _____

Hotel, meals, etc. \$ 11.2

*Show as 1/4, 2/4, 3/4, or 4/4.

Sharon M. Casey
Conservation Agent.

P. O. _____ Date _____