

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

M

File No. _____ County: Sedgwick

Location: C.S. 1/2 NE NE Sec. 14 Twp. 27 Rge. 2 (E) (W)

Name of Field: _____ Total Depth: 3261

I have this date completed supervision of plugging of:

Lease Name: Hault Well No. 4

Operator's Full Name: Jimmy Rayosh D-B-A-Maxoil Co.

Complete Address: 1915 E 21st Street, Wichita Kans

Plugging Contractor: Smith-Smith Casing Pulling Co.

Address: Cushing Okla. Box 8 License No. 205

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5 PM Day 5 Month 10 Year 60

The above well was plugged as follows:

3261' 7" Pipe set, 82' 10 3/4" surface Pipe set Cement
circulated, 3250' top Perforation. Moved to
3235' 7" pipe, and 7 sacks Cement, at 180' set
20' Rock Bridge and 30 sacks Cement, mud to
25' set 5' Rock Bridge, 10 sacks Cement which
filled hole to blow surface. Recovered 2730' 7"
Pipe

Signed: Leona Suther
Conservation Division Agent

Reviewed: Decker
Field Supervisor

Remarks:

10-18-60
INVOICED
DATE 10-19-60
INV. NO. 2366-E

Plugging

WELL LOG - HOULT #4

OPERATOR: Mr. J. P. Gaty
11 Cypress Drive
Forrest Hills
Wichita, Kansas

LOCATION: C/SL NE/4 NE/4
Section 14-27-2E
Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
Drawer 712
El Dorado, Kansas

PRODUCTION: _____

Farm: Hoult #4
Date Commenced: April 17, 1954
Date Completed: April 25, 1954

Total Depth: 3261 - Rotary

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>CABLE TOOL LOG</u>
35	82	Cement	3261 - 63½ Sand and chert
82	165	Lime	3263½ - 75½ Dolomite
165	660	Lime and shale	Cable tool T. D. 3275½.
660	1605	Shale and lime	Hole making water.
1605	2165	Lime and shale	Plugged back to 3266.
2165	2210	Shale and lime	Perforated 3250-56.
2210	2275	Lime	Oil, estimated at 30 bbls./day
2275	2448	Shale and lime	
2448	2577	Lime	
2577	2833	Lime and shale	
2833	2903	Lime and chert	
2903	2935	Cherty lime	
2935	2948	Lime	
2948	2990	Cherty lime	
2990	3030	Lime and chert	
3030	3103	Lime	
3103	3151	Kinderhook shale	
3151	3162	Hunton Lime	
3162	3180	Viola Lime	
3180	3182	S.P. Dol.	
3182	3243	S.P. Sand	
3243	3261	Sand and lime	
3261		Total Depth	

I hereby certify that the foregoing is a true and correct copy of the Well Log for the #4 Hoult well drilled for Mr. J. P. Gaty and completed April 25, 1954.

MORRISON DRILLING COMPANY, INC.

C. W. Wilson - Secretary Treasurer

STATE OF KANSAS)
) ss.
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO, Before the undersigned, a Notary Public, in and for the County and State aforesaid this 29th day of April, 1954.

Notary Public

My Commission Expires January 10, 1955.

cc made by
well log
5/12/54