

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas



File No. _____ County: Sedgewick
Location: SE-NW-NE Sec. 14 Twp. 27 Rge. 2 (E) (19)
Name of Field: — Total Depth: 3253'

I have this date completed supervision of plugging of:

Lease Name: Hault Well No. 5
Operator's Full Name: Jimmy Razook, D-B-A, Max Oil Co.
Complete Address: 1915-E 21st Street, Wichita, Kans.
Plugging Contractor: Smith-Smith Casing Pulley Co.
Address: Curlog Apts. Box 8 License No. 205
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A ✓

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____
If yes how long? _____ Reason: _____

Operation Completed: Hour 11 AM Day 8 Month 10 Year 60

The above well was plugged as follows:

3253' 7" Pipe set. 83' 10 3/4" surface Pipe set. Cement
circulated. top preparation at 3242'. hole filled
to 3235' with Honel and 7 sacks Cement. at
180' set 20' Rock Bridge and 30 sacks Cement. mud
to 25' 5' Rock Bridge and 5 sacks Cement. Reconned
2285' 7" Pipe

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION
10-18-60
OCT 18 1960
CONSERVATION DIVISION
Wichita, Kan.
INVOICED
DATE 10-19-60
INV. NO. 2367-E

Plugging Permit 910. 205
Smith & Smith
Map Sellers

WELL LOG - HOULT #5

OPERATOR: Mr. J. P. Gaty
11 Cypress Drive, Forrest Hills
Wichita, Kansas

LOCATION: SE/C NW NE
Section 14-27S-2E
Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
Drawer 712
El Dorado, Kansas

PRODUCTION: _____

Farm: Hoult - Well #5
Date Commenced: April 26, 1954
Date Completed: May 5, 1954

Total Depth: 3253' - Rotary

CABLE TOOL LOG

From	To	Formation	3253-3259 Dolomite. Oil
0	88	Cement	
88	135	Lime	
135	659	Lime and shale	
659	1036	Shale and lime	
1036	1345	Shale and lime streaks	
1345	1850	Lime and shale	
1850	2015	Sticky shale and lime	
2015	2255	Lime and shale	
2255	2290	Sticky shale and lime	
2290	2425	Lime and shale	
2425	2570	Lime	
2570	2610	Shale and lime	
2610	2834	Lime and shale	
2834	2843	Shale and lime	
2843	2921	Lime - Mississippi	
202;	2996	Lime and chert	
2996	3040	Cherty lime	
3040	3082	Lime	
3082	3141	Lime and shale	
3141	3152	Hunton	
3152	3182	Lime - Viola	
3182	3199	S.P. Sand	
3199	3252	S.P. Sand	
3252	3253	Arbuckle	
3253		Total Depth	

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Hoult #5 well drilled for Mr. J. P. Gaty and completed May 5, 1954.

MORRISON DRILLING COMPANY, INC.

C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS)
) ss:
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for the County and State aforesaid this 6th day of May, 1954.

Notary Public

My Commission Expires January 10, 1955.

to well log 5, 1954