

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 17 Twp. 8 Rge. 22 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SE SE NW

Lease Owner Harry Gore

Lease Name Culp Well No. 1

Office Address 400 Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-21 19 52

Application for plugging filed 12-21 19 52

Application for plugging approved 12-21 19 52

Plugging commenced 12-21 19 52

Plugging completed 12-21 19 52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3790 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Pipe	0	190	8-5/8	190	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 180', cemented with 15 sacks of cement.

Top plug set at 40', cemented with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 1121 Union National Bk. Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Dan J. Kornfeld (Supervisor or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
1121 Union Nat'l. Bk. Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 52

My commission expires May 5, 1956

Mary Heininger
Notary Public.

PLUGGING
FILE SEC 17-T-R-227
BOOK PAGE 68 LINE 34

RECEIVED
CORPORATION COMMISSION
DEC 31 1952
CONSERVATION DIVISION
Wichita, Kansas

LOG

COMPANY: Harry Gore & Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Culp #1
 LOCATION : SE SE NW, Sec. 17-8-22W
 Graham County, Kansas
 COMMENCED: 12-11-52
 COMPLETED: 12-21-52

0	to	30	Sand
30	to	193	Shale and shells
193	to	1160	Shale, shells and sand
1160	to	2335	Shale and shells
2335	to	2625	Shale and lime
2625	to	2735	Shale and shells
2735	to	2930	Shale and lime
2930	to	3050	Shale and shells
3050	to	3250	Shale and lime
3250	to	3350	Lime and shale
3350	to	3420	Shale and lime
3420	to	3635	Lime
3635	to	3690	Lime and shale
3690	to	3730	Conglomerate
3730	to	3790	Conglomerate (Chert) & Arbuckle
3790			T.D.

Set 190' of 8-5/8" Surface Casing, cemented with 100 sacks of cement.
 ELEVATION: 2098 R.B.

TOPS: Heebner 3320'; Toronto 3342'; L.S. K.C. 3357'; Base of K.C. 3570'; Conglomerate 3708'; Arbuckle 3754'; T.D. 3790'.

All tops taken from R.B.

D&A

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log of the Culp #1 in Section 17, Township 8 South, Range 22 West, Graham County, Kansas, as reflected by files of the Empire Drilling Company.

RECEIVED
 CORPORATION COMMISSION
 DEC 31 1952
 DEC 31 1952
 CONSERVATION DIVISION
 Wichita, Kansas

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 30th day of December, 1952.

Mary Steinmeier
 NOTARY PUBLIC

My Commission Expires May 5, 1956

PLUGGING
 FILE SEC 17 T 2 R 22 W
 BOOK PAGE 68 LINE 43