


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 29 Twp. 8S Rge. 22 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 SW/4  
Lease Owner Aurora Gasoline Company  
Lease Name Dreiling Well No. 1  
Office Address 802 Union Nat'l Bank Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Aug. 18 19 55  
Application for plugging filed Aug. 18 19 55  
Application for plugging approved Aug. 18 19 55  
Plugging commenced Aug. 18 19 55  
Plugging completed Aug. 18 19 55  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner, Great Bend, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3855 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	220'	cemented w/135 sacks cement

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole with heavy mud; set 1/3 sack hulls and Haliburton plug and 15 sacks cement; heavy mud to 35', 1/2 sack hulls, Haliburton plug and 10 sacks cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1955  
AUG 26 1955  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Veeder Supply & Development Co.  
Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.  
Leo C. Veeder (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo C. Veeder  
Cherryvale, Kansas  
(Address)


SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 55

Loles Lawson  
Notary Public.

My commission expires July 11, 1956

PLUGGING  
FILE SEC 29 T 8 R 22 W  
BOOK PAGE 144 LINE 8

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Aurora Gasoline Company  
Veeder Supply & Dev'l. Co. Farm Dreiling No. 1 Depth 3855'  
 Contractor Veeder Supply & Dev'l. Co. Pipe 220' 8 5/8" csg. cemented w/135 sacks cement  
 Location NW/4 NW/4 SW/4 Sec. 29 Twp. 8S Range 22W  
 Commenced 8-7-1955 Completed 8-18-1955 County Graham State Kansas

	0	120	120	TOPS:	
Shale					
Shale, shells, sand streaks	120	180	60	Heebner Shale	3400
Gray shale	180	350	170	Lansing K. C.	3437
Shale and shells	350	1050	700	Base K. C.	3646
Shale, shells and sand	1050	1325	275	Arbuckle	3810
Sand and shale	1325	1535	210		
Shale, shells, red bed	1535	1780	245		
Anhydrite	1780	1820	40		
Shale and shells	1820	2125	305		
Shale, shells andphyrite	2125	2315	190		
Shale and shells	2315	2425	110		
Shale and lime	2425	3355	930		
Lime	3355	3420	65		
Lime and shale	3420	3468	48		
Lime	3468	3740	272		
Lime and shale	3740	3770	30		
Lime	3770	3855	85		
T. D.	3855				

Dry and abandoned.

AFFIDAVIT

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 AUG 26 1955  
 AUG 26 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
Montgomery County) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath states that the above drilling log covering the Dreiling #1 well located in Section 29-8S-22W. Graham County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT COMPANY  
 BY Leo C. Veeder  
 Leo C. Veeder

Subscribed and sworn to before me this 20th day of August, 1955.

Colo Lawson  
 Notary Public

My commission expires July 11, 1956.

**PLUGGING**  
 WELL SEC 29 T 8 R 22W  
 PAGE 144 LINE 8