


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 29 Twp. 8S Rge. 22W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SW NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Moore Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 10 1960
Application for plugging filed June 10 1960
Application for plugging approved June 10 1960
Plugging commenced June 10 1960
Plugging completed June 10 1960
Reason for abandonment of well or producing formation No commercial quantities of oil found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	Not Pulled
				4-1/2"	3659'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raised mast, checked hole, sanded back to 3585'
Mixed and run 3 sacks cement, cleaned out cellar.
Took tension on pipe. Loaded hole with water,
Pulled cellar slips and worked tension to 27"
Checked hole and shot casing at 3055', 2992',
Worked pipe free, pulled 42 jts.
Pulled 50 jts. Bailed fluid and mudded hole to
210' set 10' rock bridge, mixed and run 25
sacks cement with dump bailer, mud to 40' set 10'
rock bridge with 10 sacks cement to base of cellar.
Well complete.

RECEIVED
STATE CORPORATION COMMISSION
July 12th
JUL 12 1960
CONSERVATION DIVISION
Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co.
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
K. J. Boone (employee of ~~owner~~ ~~operator~~ ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God, IMPERIAL OIL OF KANSAS, INC.

(Signature) By: K. J. Boone Pet. Engr.
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 1960
Merna L. Latier
Notary Public.

My commission expires July 7, 1962



Re
DRILLER'S LOG

Imperial Oil of Kansas, Inc.
 780 Fourth National Building
 Wichita 2, Kansas

Moore No. 1
 SW SW NE Sec. 29-8S-22W
 Graham County, Kansas

Total Depth: 3660'

Elevation: 2181 KB
 Production

Commenced: 6-1-60 Completed: 6-10-60

Contractor: Imperial Oil of Kansas, Inc.
 Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 210' with 175 sacks cement.
 Set 4-1/2" production pipe at 3659 with 75 sacks cement.

Figures indicate bottom of formations:

TOPS

Post Rock	50'	Anhydrite	1768 (413) Log
Sand & Shale	1100'	Heebner	3400 (-1219) Log
Shale & Hard Sand	1290'	Toronto	3426 (-1245) Log
Dakota Sand	1500'	Lansing	3439 (-1258) Log
Shale & Shells	1730'	Base Kansas City	3650 (-1469) Spl
Shale & Red Bed	1770'	Total Depth	3660 (-1479)
Anhydrite	1805'		
Shale & Shells	2125'		
Shale & Lime	3422'		
Lime	3660'		
Rotary Total Depth	3660'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By *R. J. Boone*
 R. J. Boone, Petr. Engr.

Subscribed and sworn to before me this 21st day of June, 1960.

My Commission Expires:

July 7, 1962

RECEIVED
 STATE CORPORATION COMMISSION
July 12, 1960
 JUL 12 1960

Mona L. Latier
 Mona L. Latier, Notary Public

CONSERVATION DIVISION
 Wichita, Kansas