


15-065-02036-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 30 Twp. 8S Rge. 22W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Rice Estate "G" Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 26 19 59
Application for plugging filed January 26 19 59
Application for plugging approved January 26 19 59
Plugging commenced January 26 19 59
Plugging completed January 26 19 59
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3626 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	227'	227'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with 1st plug at 500',
set with 25 sacks cement; No. 2 plug
set at 220' with 15 sacks cement; No.
3 plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
03-03-1959
MAR 3 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Milford L. Pritchard (employee of owner and operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Milford L. Pritchard Secretary
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1959

My commission expires July 7, 1962
Mona L. Latier Notary Public.

PLUGGING
FILE SEC 30 T 8 R 22W
BOOK PAGE 16 LINE 38

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

15-065-02036-00-00

Rice Estate "G" No. 1
SE SE NE Sec. 30-8S-22W
Graham County, Kansas

Total Depth: 3626'

Commenced: 1-17-59 Completed: 1-26-59

Elevation: 2186' RB
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 227' with 150 sacks cement.

Figures indicate bottom of formations:

Sand & Shale	227'
Shale-Shells & Sand	1085'
Shale & Shells	1340'
Dakota Sand	1545'
Shale & Shells	1790'
Anhydrite	1825'
Shale & Shells	2085'
Shale - Shells & Lime	2245'
Shale & Lime	2735'
Shale	2880'
Shale & Lime	3455'
Lime	3626'
Total Depth	3626'

TOPS

Anhydrite	1790'	(/ 396)
Heebner	3397'	(-1211)
Toronto	3419'	(-1233)
Lansing	3435'	(-1249)
Rotary Total Depth	3626'	(-1440)

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1959

CONFIDENTIAL DIVISION
WICHITA, KANSAS

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: W. H. Brown
Vice-President

Subscribed and sworn to before me this 4th day of February, 1959

My Commission Expires:

July 7, 1962

Meredith S. Butler
Notary Public

PLUGGING			
FILE	SEC. 30	T. 8	R. 22W
BOOK	PAGE 16	LINE 38	