


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-20837-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 30 Twp. 8S Rge. 22 ~~NE~~W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE



Locate well correctly on above  
Section Plot

Lease Owner The Maurice L. Brown Company  
Lease Name RICE "A" Well No. 1  
Office Address 1500 Vickers/KSB&T Building Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed June 17 1976  
Application for plugging filed (verbally) June 17 1976  
Application for plugging approved (verbally) June 17 1976  
Plugging commenced June 17 1976  
Plugging completed June 17 1976  
Reason for abandonment of well or producing formation No commercial quantity of gas or oil encountered.  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3710'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	231.44 K.B.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st Plug set @ 800' with 70 sacks  
2nd Plug set @ 215' with 20 sacks  
Bridge & Plug set @ 40' with 10 sacks  
50/50 Posmix Cement, 6% gel.  
State Plugger: Leo Massey  
Plug was down @ 6:30 a.m. on June 17, 1976

06-22-1976

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK  
I, Jerry A. Langrehr, Exec. V. P. (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, KS 67202 (Address)

Subscribed and sworn to before me this 21st day of June 19 76

My commission expires July 21, 1979

Sandra Richman Notary Public



CONTRACTOR'S WELL LOG

15-065-20837-00-00

OPERATOR: The Maurice L. Brown Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: RICE "A", #1  
 LOCATION: SE SE SE Section 30-8S-22W  
 Graham County, Kansas  
 SPUD DATE: June 9, 1976  
 COMPLETION DATE: June 17, 1976

0	243	Surface Clay & Shale
243	1320	Shale
1320	1575	Sand & Shale
1575	1807	Shale
1807	1843	Anhydrite
1843	2912	Shale
2912	3103	Lime & Shale
3103	3290	Shale
3290	3440	Shale with Lime Streaks
3440	3514	Lime & Shale
3514	3710	Lime
	3710	Rotary Total Depth

Drilled 243' of 12 1/4" hole. Ran 5 jts. 24# 8 5/8" casing, tallied 224.44'. Set @ 231.44 K.B. with 190 sx. Calss "A" cement, 3% ca. cl. Cement did circulate. Plug was down @ 4:30 p.m. June 9, 1976.

PLUGGED AND ABANDONED: 1st Plug was @ 800' with 70 sx. cement. 2nd Plug was @ 215' with 20 sx. cement Bridge & Plug @ 40' with 10 sx. cement. 50/50 Posmix Cement, 6% gel. State Plugger: Leo Massey. Plug was down @ 6:30 a.m. on June 17, 1976.

SAMPLE TOPS:

Anhydrite 1808'  
 B/Anhydrite 1848'

06-22-1976

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Exec. Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the RICE "A" #1, SE SE SE, Section 30-8S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
 Jerry A. Langrehr-Exec. V. P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 21st day of June, 1976.

Sandra Richman  
 Sandra Richman - Notary Public

My Commission Expires: July 21, 1979.

