

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-22860-00-00
API NUMBER 15-065-22,8600000

LEASE NAME Rice Trust

WELL NUMBER 1

330 Ft. from N Section Line

1,650 Ft. from E Section Line

SEC. 30 TWP. 8S RGE. 22 (R) or (W)

COUNTY Graham

Date Well Completed 12-10-02

Plugging Commenced 12-10-02

Plugging Completed 12-10-02

12-17-2002
1722
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Russell Oil, Inc.

ADDRESS PO Box 1469, Plainfield, Illinois 60544

PHONE (815) 609-7000 OPERATORS LICENSE NO. 3,293

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-9-02 (date)

by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	208'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Push bridge plug to 1,750', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 1,006', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 258', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mousehole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RUSSELL OIL, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor


(Employee of ~~XXXXXX~~) or ~~XXXXXX~~
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 16th day of December, 2002

My Commission Expires: _____



Ruth Phillips
Notary Public

CR




15-065 - 22860-00-00
Shields

Russell, Kansas

WELL LOG

Operator: Russell Oil, Inc.
Well: Rice Trust #1
Commenced: December 2, 2002
Completed: December 10, 2002
Contractor: Shields Drilling Co.

Well Description: NE NW NE
Sec. 30-8S-22W
Graham CO., KS



Elevation: 2,181' KB
Treatment:
Production: D & A
Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	208'	Cmtd. w/150 sax

RECEIVED
DEC 17 2002
KOC WICHITA

..... Figures Indicate Bottom of Formations

Shale & sand	110'
Shale	211'
Shale & sand	1,745'
Shale	1,785'
Anhydrite	1,822'
Shale	3,130'
Shale & lime	3,265'
Lime	3,680' RTD