


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-00433-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 31 Twp. 8 Rge. 22 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Bennett & Roberts Drilling Co.  
Lease Name Heffelfinger Well No. 1  
Office Address Drawer 232, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed June 1, 1954 19  
Application for plugging filed June 2, 1954 19  
Application for plugging approved June 3, 1954 19  
Plugging commenced June 1, 1954 19  
Plugging completed June 1, 1954 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4105 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	208	None
				5 1/2	None	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 200' w/heavy mud, pushed bottom plug to 200', cemented w/15 sx. cement and 1/2 sx. Hulls, filled hole to 40', cemented w/10 sx. cement and 1/2 sx. hulls. Job Completed @ 6:30 P.M. Tearing Down.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1954  
06-05-1954  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bennett & Roberts Drilling Co.  
Address Drawer 232 Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, SS. Harold Wurst  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Harold Wurst  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1954  
Lillian J. Salmer  
My commission expires 11-28-56 Notary Public.

PLUGGING  
FILE SEC 31 T 8 R 22 W  
BOOK 38 PAGE 38

15-065-00433-00-00

Bennett & Roberts Drig. Co.  
Hoffelinger #1

SWC Dec. 21-8-22  
Graham County, Kansas

N.T.O. 4105

Casing  
3 5/8" Set @ 200 w/140 lbs. cement

Comm: 5/21/24  
Comp: 6/1/24

Formation:	Depth:
Surface Clay	10
Sand - Strs. of post rock	100
Sand - Clay & shale	150
Shale and sand	175
Blue shale	207
Shale (Soft)	265
Shale (Hard Sandy)	280
Shale & Shells	1075
Sand & shale	1215
shale & shells	1310
Sand	1400
Shale & Sand	1620
Sand shells & shale	1900
Red rock and shale	1970
Arby.	2010
Shale & lime	2190
Lime	2240
Shale & Shells	2400
Shale & Lime	2630
Lime	2720
Lime & Shale	2770
Lime	2820
Lime & shale	2854
Lime	2916
Lime & Shale	3011
Shale & Chert	4040
Chert	4057
Dolomite	4105

STATE OF KANSAS }  
RUSSELL COUNTY } ss.

I hereby certify that the above information is true and correct to the best of my knowledge.

Lorita Bond

Subscribed and sworn to before me this 2nd day of June, 1924.

William A. Johnson  
Notary Public

My commission expires 11/20/24.

RECEIVED  
STATE CONSERVATION COMMISSION

1924  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE NO. 3178 226  
BOOK PAGE 38 LINE 38