

STATE OF KANSAS
STATE CORPORATION COMMISSION
205 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-20518-00-00

API NUMBER n/a

LEASE NAME Hull

WELL NUMBER 1

SPOT LOCATION SE NE SW

SEC. 32 TWP. 8 SRGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 1/17/72

Plugging Commenced 7/25/85

Plugging Completed 7/25/85

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 North Water, Suite 300; Wichita, Kansas 67202

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6; Hays

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation LKC Depth to top 3493 bottom 3710 T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	208'	----
				5 1/2"	3813'	----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Connected to 5 1/2" csg. Pumped 50 sacks 60/40 Pozmix w/8% gel, 3%CC and 2 sacks hulls. Followed by 20 sacks gel and 100 sacks cement (same mix) w/2 sacks hulls. SIP-300#. Calculated volume pumped down the 5 1/2" csg. is equivalent to 5277'. Connected to 8 5/8" and 5 1/2" annulus and pressured instantly to 500#. Approved by Carl Goodrow w/KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company

License No. 6033

Address 250 North Water, Suite 300; Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas

COUNTY OF Sedgwick, ss.

Pat Canaday, Hill City District, Jr. Engineer (employee of operator) (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 130, Hill City, KS. 67642

SUBSCRIBED AND SWORN TO before me this 14 day of August, 19 85



[Signature]
Notary Public

My Commission expires: 6/24/89