

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Kriley
 Location 330' North and 330' West of S/4 Cor. Sec. 24 T. 8 R. 16W
 Elevation 2000' (1997 Cr.) County Rooks State Kansas
 Drlg. Comm. October 3, 1953 Contractor Breden Drilling Company
 Drlg. Comp. October 21, 1953 Acid 1000 gals. 10-22-53
 T. D. 3417' Initial Prod. 123 oil, 5 water, 24 hrs. (11-12-53)

CASING RECORD:

8-5/8" @ 240' cen. 175 cc cement
 5-1/2" @ 3411' cen. 175 cc cement

FORMATION RECORD:

lime	0-50
chalk	90
sand	130
shale & shells	410
sand, shale & shells	1245
red bed	1325
anhydrite	1365
shale & shells	1975
broken lime	2160
lime	2200
broken lime & shale	2655
shale	2940
broken lime	3015
lime & shale	3065
broken lime	3120
lime	3271
lime & shale	3332
lime	3417
lime	3417 RTD = 3413 SLM
lime	3417 T. D.

Corr. Topsia	2900'
Corr. Heehrier	3109'
Corr. Dodge	3127'
Corr. Lansing	3150'
Corr. Arbuckle	3410'
Penetration	7'
Total Depth	3417'

11 gals. oil per hr.

RECEIVED
 STATE CONSERVATION DIVISION

MAR 14 1966
 MAR 14, 1966
 CONSERVATION DIVISION
 Wichita, Kansas

250'	1°
750'	1°
1250'	0°
1750'	0°
2250'	0°
2750'	2°
3250'	3°
3380'	1°

116-05 Reamed 20 w/1500 gal

7-7/8" rotary hole.

5-14-55 Acidized w/1500 gal by Halliburton

2-24-55 Pumped 30-4-24

2000' & 7-21' and 16-60