

PEARL McMILLEN NO. 4
NE SW SE SECTION 24-85-16W
ROOKS COUNTY, KANSAS

Owner: Stanolind Oil & Gas Company
Contractor: Transit Corporation

Formation Log
(Drillers Log)

<u>Formation</u>	<u>Depth-Feet</u>
Elevation	2008' DF
Surface Clay	0-40
Shale & Shells	40-254
8-5/8" Csg w/175 Sx. (Cmt. Circulated)	254
Shale	254-560
Sand	560-1025
Red Bed and Sand	1025-1330
Anhydrite	1330-1370
Red Bed, Shale & Shells	1370-1590
Shale & Shells	1590-2090
Lime & Shale	2090-2908
Lime	2908-3073
Lime & Shale	3073-3117
Lime	3117-3132
Shale (Heebner)	3132-3135
Lime (Lansing 3174')	3135-3400
Shale	3400-3434
Conglomerate	3434-3510
Cherty Conglomerate	3510-3527
Conglomerate	3527-3655
Lime	3655-3830
Lime, Sand & Chert	3830-3837
Granite	3837-3844
TD	3844
5-1/2" Csg w/200 Sx. Cmt	3844
DV Tool @ 1363' w/400 Sx. (Cmt Circulated)	3560