

**KANSAS DRILLERS LOG**


API No. 15 — 163 — 20751-00-00  
 County Number

S. 35 T. 8S R. 18 <sup>R</sup>W

Loc. SE NE NW

County Rush Rocks

640 Acres  
N



Elev.: Gr. 1989

DF 1992 KB 1994

Operator  
Abercrombie Drilling, Inc.

Address  
801 Union Center, Wichita, Kansas 67202

Well No. 2 Lease Name Radke "B"

Footage Location  
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Abercrombie Drilling, Inc. Geologist Vic Reiserer

Spud Date October 31, 1977 Total Depth 3460' P.B.T.D.

Date Completed November 9, 1977 Oil Purchaser

**CASING RECORD**

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"		206.71KB	Common	150	2% gel 3% CaCl

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1977  
NOV 15 1977  
CONSERVATION DIVISION  
WICHITA, Kansas

**INITIAL PRODUCTION**

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS  
Oil Gas Water Gas-oil ratio  
bbls. MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian, (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

15-163-20751-00-00

Operator Abercrombie Drilling, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry hole
Well No. 2	Lease Name Radke "B"	
S 35 T 8S R 18 W		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST#1 (3120-3153) 30", 45", 60", 45". Recovered 120' gip, 5' free oil, 15' hocr - 40% oil IFP 32-32, FFP 32-43, SIP 161-107. Temp 98.			SAMPLE TOPS:	
DST#2 (3300-3332) 30", 45", 60", 45". Weak blow. Recovered 80' oil & mud cut water - 1% oil. IFP 32-32, FFP 43-53, SIP 247-237. Temp. 103.			Anhydrite B/Anhydrite Topeka Heebner	1341 (+653) 1374 (+620) 2909 (-915) 3121 (-1127)
DST#3 (3324-3346) 30", 30", 30", 30". Weak blow - 10 min. & died. Recovered 5' mud. FP's 10-10, IBHP 32, FBHP 21.			Toronto Lansing Arbuckle	3142 (-1148) 3163 (-1169) 3415 (-1432)
DST#4 (3386-3426) 30", 45", 60", 45". Weak to fair blow. Recovered 65' frothy oil FP's 64-64, IBHP 887, FBHP 675.			ELECTRIC LOG TOPS	
Clay & shale	0	210	Anhydrite	1340 (+654)
Shale & sand	210	1347	B/Anhydrite	1376 (+618)
Anhydrite	1347	1374	Topeka	2908 (-914)
Shale & sand	1374	1841	Heebner	3120 (-1126)
Shale	1841	2294	Toronto	3142 (-1148)
Shale & lime	2294	3153	Lansing	3162 (-1168)
Lime	3153	3176	B/KC	3387 (-1393)
Shale	3176	3265	Arbuckle	3416 (-1422)
Lime	3265	3332	ELTD	3461 (-4167)
Shale & lime	3332	3346	RTD	3460 (-1466)
Lime	3346	3357		
Lime & shale	3357	3426		
Lime	3426	3460		
Rotary Total Depth	3460			

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1977  
NOV 15, 1977  
CONSERVATION DIVISION  
Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p><i>Jack L. Partridge</i> Signature</p> <p>Jack L. Partridge, Ass't. Secretary-Treasurer Title</p> <p>November 14, 1977 Date</p>
---------------	--