

MAR 18 1973

KANSAS DRILLERS LOG

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.
 20, 185 - 00-00


API No. 15 — 163 —
 County Number

S. 31 T. 8S R. 19 W

Loc. NE NW NW

County Rooks

640 Acres
 N



Locate well correctly

Elev.: Gr. 2028'

DF _____ KB 2033'

Operator
 Black Petroleum

Address 45 O. W. Garvey Building
 Wichita, Kansas 67202

Well No. #1 Lease Name Lowry

Footage Location
 330 feet from (N) (S) line 860 feet from (E) (W) line

Principal Contractor Red Tiger Drilling Co. Geologist H. F. Filson

Spud Date March 13, 1973 Total Depth 3523' P.B.T.D.

Date Completed March 20, 1973 Oil Purchaser None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	248.60	common	175	3% HA 5

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 27 1973
 CONSERVATION DIVISION
 Wichita, Kansas
 3/27/73

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Thomas E. Black, d/b/a
BLACK PETROLEUM COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. 1 Lease Name LOWRY

S 31 T 8 R 19 ^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>DRILLER'S LOG</u>				
Clay, Post Rock & Shale	0	250	RECEIVED STATE CORPORATION COMMISSION 3/27/73 MAR 27 1973 CONSERVATION DIVISION Wichita, Kansas	
Shale	250	265		
Shale & Sand	265	1335		
Shale	1335	1541		
Anhydrite	1541	1577		
Shale	1577	1975		
Shale & Lime	1975	3040		
Lime	3040	3523		
Top Anhydrite	1541	1584		
Base Anhydrite	1584	3004		
Topeka Lansing	3004	3212		
Heebner Shale	3212	3238		
Toronto Lansing	3238	3252		
Lansing	3252	3467		
Base Kansas City	3467	3503		
Arbuckle Dolomite	3503	3523		
R.T.D	3523			
DST #1: 3368-3455' (Lansing) Open 1 hr. weak blow 5" & died. Recovered 20' Mud. IF: 79# IBHP: 142# FF: 79# FBHP: 94# Temp. 108 degrees.				
			Electra, Inc. Radiation Accurlog	3524'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Thomas E. Black</i> Signature
	Owner _____ Title
	March 26, 1973 Date