

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-163-30329-00-01-~~02~~

MAR 27 1975  
03-27-1975  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Gulf Oil Corporation

Complete Address P. O. Box 12116, Oklahoma City, Oklahoma 73112

Lease Name F. Hinkhouse Well No. 5

Location C SE SW NE Sec. 6 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3838'

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 25 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 3838' 8 5/8 csg set 1777' cwc 650 sk.

5 1/2 csg set 3836' cw 100 sk.

5 1/2 csg PBTB 3730' with top perf. (3532-3536) Set plug 3500-5 sk cem.

Cutoff & recovered A/2100' of 5 1/2 csg.

Drlg. mud to 700' -set rock & sand bridge- dumped 3 yds RM cem. (700-475)

Filled with mud to 225' set rock & sand bridge -dumped 3 yds RM cem. (225-ibase of cellar.)

I hereby certify that the above well was plugged as herein stated.

Signed: Les L. Massey  
Well Plugging Supervisor

INVOICED

DATE 4/1/75  
INV. NO. 1072-W