

15-163-03015-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 107-28 County: Rooks

Location: SE NW SE Sec. 6 Twp. 10 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3855

I have this date completed supervision of plugging of:

Lease Name: Hinkhouse Well No. 4

Operator's Full Name: Gulf Oil Corp

Complete Address: c/o Degen Pipe & Supply Box 107 Rock Fork Station
Tulsa, Okla

Plugging Contractor: Bert Self

Address: Hutchinson, Kans License No. 48

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 3 Month 7 Year 58

The above well was plugged as follows:

8 5/8" at 1775' circulated with 725 sax cement - 6" OD at 3850' with
50 sax cement behind.

Filled with sand to 3820', set 5 sax cement with dump bailer, pulled
3400' 6" to 500', circulated hole with heavy mud through 6" (35 sax
Gel), displaced 20 sax cement through 6" at 450', heavy mud to 150',
displaced 20 sax cement through 6", heavy mud to 35', set bridge and
10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

07-09-1958
PLUGGING
FILE SEC. 6 T. 10 R. 20W
BOOK PAGE 107 LINE 28