

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-163-02040-00-00

API Number 15- - N/A

245 North Water
Wichita, KS 67202

Operator's Full Name SIERRA PETROLEUM COMPANY, INC.

Complete Address P.O. BOX 247 WICHITA, KANS. 67201

Lease Name DOWNEY Well No. #4

Location SE-NE-SW Sec. 10 Twp. 10 Rge. 20 (East) (West)

County ROOS Total Depth 3791 FT

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor WELSO CASING PULLING (MINE WELSO)

Address BOX 176 CHASE, MS. 67524 License No. 683

Operation Completed: Hour: 11:20 AM Day: 30 Month: DEC Year: 1980

The above well was plugged as follows:

8 5/8" 200 ST SR CUE w/ 150 ST CMT. -> 5 1/2" SET @ 3790 FT w/ 75 ST CMT.

PACER STUCK AT 3378 FT -> 550 FT TUBING IN HOLE + SOME RODS.

SQUEEZED FROM 1601 FT TO 901 FT NO PIPE RECOVERY.

ORDERED 200 ST 50/150 PREMIX 6% GEL -> 20 ST GEL -> 6 ST HULL'S.

PUMPED IN WITH PUMP TRUCK.

PUT IN 5 1/2" -> 25 ST CMT. -> 10 ST GEL. -> 25 ST CMT. -> 10 ST GEL. -> 1 ST HULL'S

55 ST CMT. -> 3 ST HULL'S - AND 35 ST CMT. MAX PRESSURE 1200 LBS

PUMPED IN ANNULUS 25 ST CMT. -> 2 ST HULL'S AND 25 ST CMT.

MAX. PRESSURE IN ANNULUS 600 LBS

CEMENTED BY ALLIED CMT.

DEC 31 1980
12-31-1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICE
DATE 1-12-81
INV. NO. 3863-W