

P

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163 - 20224 - 00 - 00

Operator's Full Name Donald C. Slawson,  
Complete Address 408 One-Twenty Building, Wichita, Kansas.  
Lease Name Teall Well No. A-1  
Location NE-NW-SE Sec. 17 Twp. 10 Rge. (E) (W) 20  
County Rooks Total Depth 3570'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Slawson Drilling Company, Incorporated,  
Address 408 One-Twenty Building, Wichita, Kansas License No.         
Operation Completed: Hour 9:30 PM Day 26 Month 9 Year 1969

The above well was plugged as follows:

179'---8 5/8" Surface casing, cement circulated with 160 Sx.  
Circulated hole with heavy mud. Pulled DP to 875' and displaced 100 Sx. cement thru  
DP from 875' to 550'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from 185'  
to 125'. Pulled DP, set bridge @ 40' with 1/2 sack bulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
07-01-1969  
JUL 1 1969

I hereby certify that the above well Wichita, Kansas plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 7-1-69  
INV. NO. 30-W