

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
01-07-1969

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163 - 20163-00-00

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address: 400 N. Woodlawn Wichita, Kansas

Lease Name Romine Well No. 3747. 1

Location NW NE SE Sec. 19 Twp. 10 Rge. 20 (E) (W) XX

County Rooks Total Depth 3747

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Sage Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 4:15P Day 1 Month 1 Year 1969

The Above well was plugged as follows:

RTD 3747' 8 5/8 csg set at 244' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 1/7/69  
INV. NO. 9155-W

Signed: [Signature]  
Well Plugging Supervisor