

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 033-21240 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: Bear Petroleum, Inc. KCC License #: 4419
(Owner / Company Name) (Operator's)

Address: P.O. Box 438 City: Haysville

State: KS Zip Code: 67060 Contact Phone: (316) 524 - 1225

Lease: K & G Well #: 1 Sec. 11 Twp. 32 S. R. 20 East West

C - SW - SE - SE Spot Location / QQQQ County: Comanche

353 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

863 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 20" Set at: 55' Cemented with: 5 yards Sacks

Surface Casing Size: 8 5/8" Set at: 756' Cemented with: 375 Sacks

Production Casing Size: 4 1/2" Set at: 5274' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs 5118-28

Elevation: 1968 (G.L. / K.B.) T.D.: 5284 P.BTD: 5217 Anhydrite Depth: ?

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): According to the rules and regulations of the KCC.

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

MAR 03 2008

if not explain why? _____
CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: R. A. (Dick) Schremmer
Bear Petroleum, Inc. Phone: (316) 524 - 1225

Address: P.O. Box 438 City / State: Haysville, KS 67060

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529
(Company Name) (Contractor's)

Address: P.O. Box 467, Chase, KS 67524 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 2-29-08 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

replacement card

J-F OIL COMPANY L'
HAYS KS 67601

11-32S-20W
353' FSL & 863' FEL, SEC

#1 K & G

site 6-1/2 W OF COLDWATER KS	city: COMANCHE	API 15-033-21240
contr: ALLEN DRILLING #4	field: PROTECTION NW EXT (1/4 N)	
geol: KIM B. SHOEMAKER		
fr date 07/09/2001	spd date 08/30/2001	drig comp 09/12/2001
		card issued 12/17/2001
		last revised 03/17/2003

ELV: 1968 KB, 1952 GL LOG
tops.....depth/datum
HEEB.....4208 -2240
BR LM.....4390 -2422
LANS.....4411 -2443
STARK.....4740 -2772
BKC.....4865 -2897
MARM.....4920 -2952
ALT.....4938 -2970
PAW.....4984 -3016
CHER.....5020 -3052
MISS.....5118 -3150
LTD.....5275 -3307
RTD.....5284 -3316

IP status:
GAS, COF 1,071 MCFGPD & WTR, MISS 5118-5128 , 09/17/2001
 INFO RELEASED: 3/17/2003 - WAS GAS WELL - TIGHT HOLE
 CSG: 20" COND AT 55 / 5 YDS GROUT, 8-5/8" 756 / 375 SX (ALT 1), 4-1/2" 5274 / 150 SX
 COMMENT: MI & RURT 8/29/2001; OPTIONAL LOG TOP - IATAN 4390 (-2422)
 SHOWS: 5009-5012 (PAW LM, PR PORO, TR SPTD STN, TR SFO, TR SG, FR SPTD FLUOR, NO ODOR), 5158-5180 (MISS LM, FR-PR PNPT PORO, TR SFO, TR SG, FR SPTD FLUOR, NO ODOR), 5180-5190 (MISS LM, PR PORO, TR STN, VSSF, TR SG, FR-GD FLUOR, NO ODOR), 5190-5200 (MISS LM, FR PORO, TR STN, TR SFO, TR SG, FR SPTD FLUOR, NO ODOR).

COPYRIGHT 2003
INDEPENDENT OIL & GAS SERVICE INC

OIL COMPANY LLC
HAYS KS 67601

11-32S-20W
353' FSL & 863' FEL, SEC

#1 K & G

200-5210 (MISS LM, SME CHT, PR PORO, TR STN, TR SFO, TR SG, FR SPTD FLUOR, NO ODOR),
 258-5260 (MISS LM, CHLKY, TR CHT, PR PORO, TR STN, TR SFO, FR SPTD FLUOR, NO ODOR)
 O CORES
 1ST (1) 5126-5158 (MISS), / 15-45-45-90, (1ST OP) SB OFF BTM BKT/IMMED, GTS/2", GA 1080 MCFG/5",
 198 MCFG/10", 1274 MCFG/15", THRU 1-1/2 INCH CK, ISI: WK SURF BLO BK, (2ND OP) SB OFF BTM
 KT/IMMED, GA 1160 MCFG/5", 1274 MCFG/10", 1311 MCFG/15" THRU 35", 1292 MCFG/40" & 45", FSI:
 /K SURF BLO BK, REC 20' WM (40% W, 60% M, RW M 0.18 OHMS AT 94 F, CHL 26,000 PPM;
 W MF 0.22 OHMS AT 89 F, CHL 24,000 PPM; RW PS 0.56 OHMS AT 80 F, CHL 10,000 PPM, RW PSF
 58 OHMS AT 82 F, CHL 9500 PPM) ISIP 1830# FSP 1801# IFP 228# -248# FFP 244# -239# IHP 2520#
 -IP 2361# BHT 111
 RGT ZN: MISS (OIL/GAS), PTD 5300 (MISS), MICT - CO, PF (MISS) 5118-5128, W / 4 SPF, AC 1500 GAL
 5% FE), SWB LD, GSG, SET 2-3/8" TBG AT 5092, NO PKR, SI, GAS WELL (POTENTIAL NOT RPTD),
 17/2001; STATE TST: 1-PT COF 1071 MCFGPD & WTR, THRU 3/4 INCH CK, CP 1292#, FTP 1061#,
 2/2002

K. G. S. LIBRARY

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 03 2008

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BEAR PETROLEUM, INC.
PO BOX 438
HAYSVILLE, KS 67060-0438

March 05, 2008

Re: K AND G #1
API 15-033-21240-00-00
11-32S-20W, 353 FSL 863 FEL
COMANCHE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after September 1, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888